




- NOTE:
- ALL DIMENSIONS ARE IN METERS, UNLESS OTHERWISE SPECIFIED.
 - EXISTING WORK SHOWN IN BLACK.
 - PROPOSED WORK SHOWN IN RED.
 - AS PER TERMS OF REFERENCE YARD GRADIENT HAVE BEEN EASED TO THE EXTENT POSSIBLE MAINTAINING GRADIENT AS 1 IN 150 (COMPENSATED).
 - RAIL LEVEL SHOULD BE 762 MM ABOVE FORMATION LEVEL FOR TRACK STRUCTURE OF 60 KG NEW RAIL ON PSC WIDER SLEEPER (1660 NOS PER KM) WITH 350 MM BALLAST CUSHION.
 - RULING GRADIENT OF THIS SECTION IS 1 IN 150.
 - AS PER ENGINEERING CODE, VERTICAL CURVE WILL BE PROVIDED AT SITE WHERE ALGEBRAIC DIFFERENCE BETWEEN TWO GRADES IS EQUAL OR MORE THAN 4MM PER METER OR 0.4%.
 - LAND TO BE ACQUIRED SHOWN IN DASHED RED.
 - THE CHAINAGE AND KILOMETERS SHOWN ARE RECKONED FROM CENTER LINE OF STATION BUILDING AS 0.00
 - THE SECTION IS DESIGNED FOR MAXIMUM SECTIONAL SPEED OF 160 KMPH.
 - THE PROPOSED FORMATION AND BRIDGES IN THE SECTION IS DESIGNED FOR 25 T-2008 AXLE LOADING.

TBM DETAILS					
TBM ID	Chainage	Easting	Northing	MSL	Description
BM11	1280183.577	762137.399	3038043.78	180.688	Marked on the KM Stone Base Near Railway Track.
BM10	1280910.002	762535.605	3038649.739	179.688	Marked on the EP Base Near Railway Track.
BM9	1281668.371	762918.482	3039303.866	178.688	Marked on the EP Base Near Railway Track.
BM8	1282307.777	763259.235	3039845.622	177.688	Marked on the EP Base Near Railway Track.
BM7	1283348.641	763786.198	3040741.818	176.688	Marked on the EP Base Near Railway Track.

LEGENDS:	
EXISTING RAILWAY TRACK	EXISTING ROW
PROPOSED RAILWAY TRACK	METAL ROAD
PROPOSED ROW	UN-METAL ROAD
PRO. BRIDGES	
ELECTRIC LINES	
HT LINES	
WATER BODIES	
RAILWAY STRUCTURES	

ABBREVIATIONS	
R = Radius	PVI = Point of Vertical Intersection
Δ = Angle	TTT1 = Tangent to Transition Point-1
TRL = Transition Length	CTP1 = Curve Tangent Point-1
TL = Tangent Length	CTP2 = Curve Tangent Point-2
SL = Straight Line Length	TTT2 = Tangent to Transition Point-2
CL = Curve Length	BVC = Beginning of Vertical Curve
CCL = Circular Curve Length	EVC = End of Vertical Curve
IP = Intersection Point	ERL = Existing Rail Level
RTL = Road Top Level	BL = Bed Level

REFERENCE DRAWINGS	
DRAWING TITLE	DRAWING No.
DRG.No.DY.CE/C/KOTA	
H.Q. DRG. NO.- CPM/KOTAVE	
NAME OF THE OFFICER & DESIGNATION	SIGNATURE
(VIJAY PANDEY) CPM/WCR/KOTA	
(GAURAV MISHRA) DY.CE/C/KOTA	
(RAJESH YADAV) AXEN/KOTA	
(P.K. KANWA) SSE/WCR/KOTA	
(L.S. MEENA) JE/DRG/KOTA	

ISSUE RECORD				
No.	DATE	REV	PREPARED BY	CHECKED BY
1	01-07-2025	R0	SIVA THUTA	RAMMOHAN
				RAMAKRISHNA

CLIENT:	WEST CENTRAL RAILWAY KOTA DIVISION
---------	---------------------------------------

PROJECT : CONDUCTING FINAL LOCATION SURVEY (FLS) INCLUDING PREPARATION OF DPR, GEOTECHNICAL INVESTIGATION, SIGNALING WORK, ELECTRICAL WORKS AND OPERATING/TRAFFIC WORK FOR CONSTRUCTION OF ELECTRIFIED NEW LINE/DOUBLING/THIRD LINE/4TH LINE. FLY OVER WORK/BYPASS LINE ETC.

TITLE : DETAILED PLAN AND L SECTION MATHURA-NAGDA -3RD LINE 1280+000.000 TO 1283+808.276

CONSULTANT : aarvee engineering consultants limited.

DRG.No: AA/WCR/FLS/2616/MKN-3RD/P&P/110	SHEET NO : 110
SCALE : HOR : 1:5000 , VER : 1:500	DATE : 01-07-2025